

PART 1 – GENERAL

1.1 SUMMARY

This Section covers control of dust resulting from construction operations of the Project.

PART 2 – PRODUCTS

2.1 GENERAL

Water to be used for dust control on the Project shall be potable or non-potable water obtained from a source approved by the Owner or as directed by the Owner's Authorized Representative (OAR) in accordance with the applicable requirements.

PART 3 – EXECUTION

3.1 GENERAL

- A. Prior to the start of construction, the Contractor must submit a Dust Control Plan which will describe the means and methods to alleviate and prevent dust nuisance originating from construction operations including but not limited to demolition, earthwork, crushing, hauling and stockpiling operations within the Project limits inclusive of the staging yard. Work shall not commence until the Dust Control Plan has been approved by the OAR.
- B. The Contractor will investigate the availability of an adequate supply of suitable water, make all arrangements (including permit if required) for the purchase of the water and provide necessary facilities to furnish water for use during construction, solely at the Contractor's expense. Water may be obtained from the fire hydrants on Airport property. The availability and quality of the water obtained from these sources is not guaranteed.
- C. Any dust control complaints received from tenants, airport users, and or the Airport Operations Department shall require the Contractor to cease dust creating tasks until such time that the dust control measures have been implemented and the issue resolved.

PART 4 – MEASUREMENT AND PAYMENT

Not Used.

– END OF SECTION –